



JAWAHAR VIDYA MANDIR
SHYAMALI, RANCHI – 834002

जवाहर विद्या मंदिर, श्यामली, राँची- 834002



Ref.: JVM/OT-02/2016-17

Dated :10-05-2016

INVITATION TO TENDER

Subject: REPAIR OF 1000 NOS. OF STUDENTS DESKS AND REPLACEMENT OF TOP PLY BOARD WITH LAMINATE OF JAWAHAR VIDYA MANDIR SHYAMALI

Sealed Tender are Invited for REPAIR OF 1000 NOS. OF STUDENTS DESKS AND REPLACEMENT OF TOP PLY BOARD WITH LAMINATE OF JAWAHAR VIDYA MANDIR SHYAMALI

All interested parties may download the tender documents from JVM site (www.jvmshyamali.com)

Last date & time of submission of Tender is 21-05-2016 up to 12.00 noon.

Cost of tender papers is Rs 1000/- (Rs one thousand only), non-refundable payable by Demand draft in favour of Jawahar Vidya mandir Shyamali, Ranchi shall be deposited alongwith the submitted tender.

Tenders submitted without DD shall be rejected.

(A.K.Singh)
Principal



Ref.: JVM/OT-02/2016-17

Dated :10-05-2016

NOTICE INVITING TENDER

WORK : REPAIR OF 1000 NOS. OF STUDENTS DESKS AND REPLACEMENT OF TOP PLY BOARD WITH LAMINATE OF JAWAHAR VIDYA MANDIR SHYAMALI

Dear Sir

The Principal, Jawahar Vidya Mandir ,Shyamali , Ranchi invites tender for the work to be carried out in the JVM premises.

The tenderers will have to submit their quotations in a sealed envelope to the Principal, JVM Shyamali,Ranchi-2 by 12.00 Noon on 21/05/2016 titled REPAIR OF STUDENTS DESKS

Scope of work:

The major scope of work covers the detachment of old wooden top from student's desk and fix 19 mm thick new water proof ply board with glossy finish laminates of thickness 0.8 mm. Edges will be finished with half circular teak finished beat (polished) all around the board.

List of activities shall consist but not limited to:

1. Detachment of old wooden top from student's desk
2. Fix the 19 mm thick new water proof board on the desk.
3. Fix the finish glossy laminates of thickness 0.8 mm with good quality of adhesive.
4. Finishing the edges with half circular teak finished beat all around the board. Fix the glossy laminate with good quality of adhesive.
5. Half circular beating shall be done with teak wood and properly polished.
6. All the materials supplied to the site shall be of good quality Any material which is not approved by the engineer shall be removed from the site at his own cost by the contractor
7. The work will be carried out at our premises.
8. All the wastage shall go to the account of the contractor only
9. **Completion period** : The job shall be completed in all respect within three months from the date of the placement of order..
10. **Payment** ; 80% of price shall be paid after the completion of work against RA bill. Balance 20% of price shall be released on completion of the work as per the satisfaction of site in –charge.



11. Inspection of work:

Inspection at site shall be taken up jointly by the site engineer and the contractor. In case of any dispute the decision of site engineer will be final.

12. GENERAL

- Before submission of the tender, the tenderer shall inspect the desk to study the nature and the extent of work involved and also to obtain the first hand information regarding the desk condition in school. The tenderer shall consider all aspects in the quoted rate carefully and no claim whatsoever shall be entertained later on the plea of ignorance of existing conditions or any other factors.
- Quoted price shall be inclusive of all taxes.


13 LIST OF PREFERRED MAKE:

1. Laminate
 - i) Sunmica
 - ii) Durian
 - iii) Green lam
 - iv) Century
 - v) Marino
 - vi) Decolam
2. Water proof ply board
 - i) Century
 - ii) Green ply
 - iii) Kit ply
3. Adhesive: Fevicol or equivalent make.



JAWAHAR VIDYA MANDIR
SHYAMALI, RANCHI – 834002

जवाहर विद्या मंदिर, श्यामली, राँची- 834002



PRICE FORMAT

	Description	Nos	Rate	Total Price
1	Detachment of old wooden top from student's desk and fixing 19 mm thick new water proof ply board as per IS: 303 with glossy laminates of thickness 0.8 mm with good quality adhesive . Half circular teak finished beat (polished) shall be fixed all the edges .Size of each board 24"x16" approx.	1000		

(A.K.Singh)
Principal